Work Order ID : 6277716
Please have on site contact sign this copy and keep this for your record.

General Information

Service Title
Sprint: Memory and VeriFone Upgrade

Service Schedule
On Tuesday March 12th 2019
At 10:00 am EDT

Manager of Work Order
Madison Phipps

+14792223569

Assigned Provider
Sadiqa Thornton (user id: 24217)

Service Location (type: Commercial)
629

NEWARK, NJ, 07102

On Site Contact
Pvital Support line
+17206084739

Additional Fields

Customer Ticket #
N/A

Full Work Description

FOLLOW EACH STEP ON DOCUMENTS FIRST TO LAST; IF YOU DO NOT FOLLOW STEP BY STEP THE DEVICE WILL NOT BE INSTALL PROPERLY

IF THERE IS MONEY IN THE TILL DO NOT TOUCH ASK A SUPERVISOR TO HANDLE IT BEFORE PROCEEDING

Summary of Tasks to perform:

- **Memory upgrade** – open the core PC and to Upgrade the Memory to 8GB
- **Verifone equipment Hardware upgrade** – removing the dip reader, cabling, and installing the new Verifone equipment with cabling.

Note: We are to represent as NCR field engineers.

Upgrading the following items of VeriFone devices:

- UX100 (pin-pad)
- UX 300 (Card Reader)
- UX400 (NFC Reader) into the new fascia parts
- Upgrading the PC-core memory from 4 GB to 8 GB.

CONFIRM YOU HAVE RECEIVED THE FOLLOWING EQUIPMENT BEFORE PROCEEDING WITH THE INSTALLATION:

Note: IF THERE IS EQUIPMENT MISSING IMMEDIATELY NOTIFY sprintsupport@pivital.com AND FDAR@sprint.com AND WAIT FOR FURTHER INSTRUCTIONS

Inventory Checklist:

- Verifone UX300 card reader
- UX100 pin pad
- UX400 NFC reader
- SelfServ 75 UX Device mount kit
- SelfServ 75 Memory Upgrade Kit
- printout of kit instruction(s)

Installation Tasks:

1. Program to be downloaded/installed on the unit prior to CE/installer visit to be powered down
2. hardware upgrades to be done to be powered back on the unit to come back on-line
3. test transaction to be performed to confirm the unit is operational
4. Receive Validation from the Sprint Support line***

Required tools for case:

- Laptop
- Hotspot
- Camera
- CellPhone
- Screw Driver Kit
- Socket Set
- #2 Phillips screwdriver with a torque limiter
- #7 mm nut driver with a torque limiter
- Flat Head screwdriver
- Basic Toolkit
- Wire cutters
- Ink Pens (for documentation)
- NCR Documents
- NCR Signoff
- Cable ties (*Plenty*)

Estimated 2 hours per Kiosk Device

*The assigned field engineer will be compensated for the additional time i*f a site goes over the estimated two hours due to a Sprint complication/problem.

Pre-Installation Tasks:

1. Review each of the provided documents
2. Print the NCR Customer Acceptance Form
3. Download each of the provided documents for quick access
4. Confirm with Pivital you are prepared for the opportunity 24 hours prior to the Upgrade
5. If there are any questions prior to the upgrade to reach out to the Pivital support line

Arriving & Departing the site:

CHECK IN & OUT ON FIELD NATION PLATFORM IN LIVE TIME

Please complete all of the tasks prior to leaving the site; this will include but not limited to:

1. Check in on the Field Nation Platform
2. Contact the Pivital Support line upon arrival and departure **@(720) 608-4739**.
3. Inform the Manager on Duty you have arrived on site, and ask for the Equipment that was provided by NCR.
4. Perform Inventory Check; If not all the equipment is provided you are required to send an email to**FDAR@sprint.com**
5. Complete memory upgrade
6. Complete Pin Pad upgrade
7. Test the system making sure all equipment is functioning as designed
8. Contact the Sprint Support line for validation of the working device (Required)
9. Take pictures of BEFORE and AFTER work is complete and transmit those to the Field Nation Platform in LIVE-time
10. Clean up the work area and take out the trash
11. Have the lead technician or Manager on Duty sign the NCR document **
12. Send ALL requested deliverables to **sprintsupport@pivital.com** before departing the site, and wait for approval in the documentation
13. Provide all the required deliverable to the work order
14. Provide a detailed Field log of everything that occurred onsite
15. Closeout work order completely before departing the site

*****REQUIRED DELIVERABLES TO BE SENT TOsprintsupport@pivital.com** BEFORE DEPARTING:

-The Sprint Support Reps Name*

-Signed NCR document Attached filled out correctly*

-picture of finalized UX device cabling and picture from the front with upper fascia down*

-picture of the pin pad screen showing the word Sprint*

-Notes on installation (complete, issues, feedback, etc...)*

ALL TASKS ARE REQUIRED TO BE COMPLETED BEFORE THE ASSIGNED TECHNICIAN DEPARTS THE SITE

GENERAL REQUIREMENTS:

Good hygiene, as well as a professional and clean appearance (dress code is “business casual”).

No helpers of any kind are allowed without prior consent.

Carry a photo ID/driver license while on-site.

Do not ask a customer for tools or assistance.

Arrive with the tools, supplies, and documents required to complete the work.

Contact information:

Project Manager can be reached at 479-222-3569

Pivital Support team can be reached at (720) 608-4739.

Pivital for imperative IT questions atsprintsupport@pivital.com

Sprint Help Desk Contact Process (REQUIRED FOR VALIDATION ONLY):

Step 1: Call the Sprint APC at 833-415-3046 (Do not leave voicemail)

Step 2: If no one answers at the APC, send an email to FDAR@sprint.com

Step 3: If after five minutes, and there is no email response, call Kristina Shelley at 816-305-4578.

Step 4: Start over the process if no response from Kristina

If the assign field engineer fails to provide the MOD signed NCR document, Photos requested, and field log prior to* **sprintsupport@pivital.com *before departing the site Pivital will be obligated to forfeit the technicians' payment and approval of work.*

*The assigned field engineer MUST receive verification from the Sprint Helpdesk before you are allowed to depart from the site. If the assigned field engineer leaves the site without validation you will be forfeiting payment.**

Tasks

Some tasks below may be eligible for completion by calling 1-877-573-6330

Pre Visit

1. Provider must set start time

On Site

1. Provider must check in
   (Code 119 340 172 773 9#)
2. Provider must call phone number **(720) 608-4739** **To Check into Site with Pivital**
3. Provider must **Complete Inventory Check**
   (Code 120 343 192 773 9#)
4. Provider must upload or take a picture of **Inventory**
5. Provider must upload or take a picture of **the pin pad screen showing the word Sprint**
6. Provider must **Provide Serial Number for each Kiosk that is upgraded on the NCR CAF document. (This information is located inside of the Kiosk)**
   (Code 138 347 723 773 9#)
7. Provider must upload or take a picture of **finalized UX device cabling and picture from the front with upper fascia down (LABELED)**
8. Provider must collect a signature from Of the signed NCR Customer Acceptance Form

9. Provider must call phone number **833-415-3046** **Verifying the work completed on the site (the technician is prohibited to depart site before gaining approval from the Sprint helpdesk)**

10. Provider must call phone number **(720) 608-4739** **To Check out with Pivital**

11. Provider must **Installation notes (complete, issues, feedback, etc...)**
    (Code 158 341 873 773 9#)
12. Provider must check out
    (Code 101 348 783 773 9#)

Post Visit

1. Provider must enter close out notes

2. Provider must **Label all Photos**
   (Code 149 346 104 773 9#)

Collected Signature

Signed by on paperwork On Mar 12th 2:59pm

Approval of Work

I acknowledge that the work has been satisfactorily completed.

Name

Arrival Time AM / PM

Signature

Departure Time AM / PM

Date

CONFIDENTIAL!

The following information is confidential and should not be seen by anyone but you, the assigned provider.

Deliverable Uploads

Make sure you collect and upload any required deliverables into the following deliverable categories:
[ ] Inventory
[ ] the pin pad screen showing the word Sprint
[ ] finalized UX device cabling and picture from the front with upper fascia down (LABELED)
[ ] Misc

Customer Standard Instructions

-Deliverables are due within 6 hours of tech leaving site.

Customer Policies & Procedures

PIVITAL Policies & Procedures

*****ATTENTION: ALL ITEMS ARE REQUIRED FOR PAYMENT****

-IMPORTANT: Present yourself as an representative of PIVITAL. **Do not promote any other company other than PIVITAL on this Work Order.**

-The requesting provider must be the provider who performs the actual service work onsite. You are expected to arrive onsite by yourself (no helpers, or assistants). Exceptions may be given but only upon prior approval by PIVITAL on this Work Order. Failure to comply with the above statements will result in loss of compensation on this work order.

-Dress Code: Business casual is required. No denim; t-shirts; logos or tennis shoes are allowed (work boots are acceptable).

-Print this work order and all additional documentation. Read the complete work order prior to arrival. Direct all questions to PIVITAL on this Work Order contact-NOT THE END CLIENT.

-Work performed outside the original Service Information detailed on this work order will not be compensated to the provider by PIVITAL on this Work Order unless it has been pre-approved by PIVITAL's Work Order manager. Requests by the provider for any payment increase must be documented in the messages tab of this work order, for any payment increase to be considered for approval. Additionally, pre-approval is required in work order messages for any expenses not in the work order when assignment occurs.

-By requesting this work order you agree to warranty all work performed on this work order to PIVITAL on this Work Order for a minimum period of 15-business days. Warranty period will begin from the date that PIVITAL on this Work Order has approved the work order electronically on the Field Nation platform. You will be required to repair all failed work, at no additional costs to PIVITAL on this Work Order within 3-business days of being notified of the warranty issue.

-You agree to provide PIVITAL on this Work Order with a 100% satisfaction guarantee. If you fail to fully complete the Services requested, then PIVITAL on this Work Order will not consider the work order complete.

-By accepting a work order you are stating that you have the expertise, tools and equipment required to perform the services in accordance with industry standards and practices.

-Acceptance of work order enters you into a legally binding contract to perform the services. By accepting this work order you agree not to solicit any business directly with PIVITAL's client that you are performing work for on this work order.

-The Spend Limit set on this work order is inclusive of all costs.

-If upon arrival you find that the work site is not ready for services you must contact the specified contact listed by PIVITAL on this Work Order prior to leaving the premises for further instructions. Failure to do so will be considered a 'No-Show' on your part.

-Deliverables are required within 12-hours of the completion of this work order. After the 12-hour threshold, a Late Closeout Penalty will be applied: 25% of labor

-Do not cancel appointments. In case of emergency contact PIVITAL on this Work Order directly. DO NOT CONTACT the End-User.

-Upon final project approval by PIVITAL on this Work Order, you will be paid by PIVITAL on this Work Order via Field Nation.